

**INTERNATIONAL ORGANIZATION FOR STANDARDIZATION
ORGANISATION INTERNATIONALE DE NORMALISATION
ISO/IEC JTC 1/SC 2/WG 2/IRG**

**Universal Coded Character Set
(UCS)**

ISO/IEC JTC 1/SC 2/WG 2/IRG N2275 WG2N2833

(Revision of IRG N1503/N1772/N1823/N1920/N1942/N1975/N2016/N2092/N2153
(N2222)
2017-10-19

Title:	IRG Principles and Procedures (IRG PnP) Version 10
Source:	IRG Rapporteur
Action:	For review by the IRG and WG2
Distribution:	IRG Member Bodies and Ideographic Experts
Editor in chief:	Lu Qin, IRG Rapporteur
References:	Recommendations from IRG #48 (IRGN2220), IRG #47 (IRGN2180), IRG #45 (IRGN2150), IRG #44 (IRGN2080), IRGN2016 and IRGN 1975, IRG #42(IRGN 1952 and feedback from HKSARG, Japan, ROK and TCA, IRG 1920 Draft (2012-11-15), Draft 2 (2013-05-04) and Draft 3 (2013-05-22); feedback from Japan (2013-04-23) and ROK (2013-05-16 and 2013-05-21); and IRG #40 discussions, IRG1823 Draft 3 and feedback from HKSAR, Korea and IRG #39 discussions IRGN1823 Draft2 feedback from HKSAR and Japan IRGN1823Draft_gimgs2_Feedback, IRGN1781 and N1782 Feedback from KIM Kyongsok, IRGN1772 (P&P Version 5), IRGN1646 (P&P Version 4 draft) IRGN1602 (P&P Draft 4) and IRGN1633 (P&P Editorial Report), IRGN1601 (P&P Draft 3 Feedback from HKSAR), IRGN1590 and IRGN1601(P&P V2 and V3 draft and all feedback), IRGN1562 (P&P V3 Draft 1 and Feedback from HKSAR) IRGN1561 (P&P V2 and all feedback) IRGN1559 (P&P V2 Draft and all feedback) IRGN1516 (P&P V1 Feedback from HKSAR) IRGN1489 (P&P V1 Feedback from Taichi Kawabata) IRGN1487 (P&P V1 Feedback from HKSAR) IRGN1465, IRGN1498 and IRGN1503 (P&P V1 drafts)

Table of Contents

1. Introduction.....	3
1.1. Scope of IRG Work	3
1.2. Scope of this Document	3
2. Development of CJK Unified Ideographs	3
2.1. Principles on Identification of CJK Unified Ideographs	4
2.1.1. Principles on Encoding	4
2.1.2. Unification Procedure of CJK Ideographs	4
2.1.3. Non-cognate Rule	4
2.1.4. Maintaining Up-to-date Unification/Non-unification Examples	4
2.2. Principles on Submission of Ideographs to the IRG	4
2.2.1. Basic Rules of Submission and Required Data to be Submitted	4
2.2.2. Required Font to be Submitted.....	7
2.2.3. Required Evidence to be Submitted	7
2.2.4. Required Summary Form to be Submitted	8
2.2.5. Quality Assurance: The 5% Rule.....	8
2.3. Principles on Production of IRG Working Drafts	8
2.3.1. Principles on Submitted Ideographs	9
2.3.2. Principles on Assignment of Serial Numbers	9
2.3.3. Principles on Machine-checking of IDS of Submitted Ideographs.....	9
2.3.4. Production of IRG Working Drafts	9
2.4. Principles on Reviewing IRG Working Drafts	10
2.4.1. General Principles on Reviews.....	10
2.4.2. Principles on Manual Checking	10
2.4.3. Submission of Possibly Unifiable Ideographs.....	10

2.5. Principles on Discussions at IRG Meetings	11
2.5.1. Document-based Discussion	11
2.5.2. Discussion Procedure	11
2.5.3. Recording of Discussions	11
2.5.4. Time and Quality Management.....	11
2.6. Principles on Submission of Ideographs to WG2	12
2.6.1. Checking of Stabilized M-Set.....	12
2.6.2. Preparation for WG2 Submission	12
3. Procedures	12
3.1. Call for Submission	12
3.2. Consolidation and Grouping of Submitted Ideographs	13
3.3. First Checking Stage	13
3.4. First Discussion and Conclusion Stage	13
3.5. Subsequent Checking Stage	14
3.6. Subsequent Consolidation and Conclusion Stage	14
3.7. Final Checking Stage	14
3.8. Approval and Submission to WG2	14
4. Guidelines for Comments and Resolutions on Working Sets	14
4.1. Guidelines for M-Set	15
4.2. Guidelines for D-Set	15
5. IRG Website.....	16
6. IRG Document Registration	16
6.1. Registration Procedure	17
6.2. Contact for IRG Document Registration	17
Annex A: Sorting Algorithm of Ideographs.....	18
Annex B: IDS Matching.....	20
B.1. Guidelines on Creation of IDS	20
B.2. Requirements of IDS Matching	20
B.3. Limitation of IDS Matching	20
Annex C: Urgently Needed Ideographs	21
C.1. Introduction	21
C.2. Requirements	21
C.3. Dealing with Urgent Requests	21
Annex D: Up-to-date CJK Unified Ideograph Sources and Source References	22
Annex E: Maintenance Procedure of the IRG Working Document Series.....	25
E.1 Introduction	25
E.2. IRG Working Document Series	25
E.3. Maintenance Procedure	25
Annex F: IRG Repertoire Submission Summary Form.....	27
Annex G: Examples of New CJK Unified Ideographs Submissions (i.e., Vertical Extension)	29
G.1. Sample Data Files	29
G.2. Sample Evidence	29
G.3. Handling of Data with Privacy Concerns	30
G.4. Consideration for Acceptance of Characters that Cannot be Provided in Printed Form	30
Annex H [Reserved for future use]	32
Annex I: Guideline for Handling of CJK Ideograph Unification and/or Dis-unification Error.....	33
I.1 Guideline for “to be unified” errors	33
I.2 Guideline for “to be disunified” errors	33
I.3 Discouragement of new disunification request	33
Annex J: Guideline for Correction of CJK Ideograph Mapping Table Errors	34
J.1 Priority of Error Correction Procedure	34
J.2 Announcement of Addition to or Correction of Mapping Table	34
J.3 Collection and Maintenance of Mapping Tables that are not owned by WG2	34
Annex K: List of First Strokes	35
Annex L: Guidelines for Forming Working Sets with an Upper Limit	36
References	37
Glossary	38

1. Introduction

This document is a standing document of the ISO/IEC JTC 1/SC 2/WG 2/IRG for the standardization of Chinese-Japanese-Korean (CJK) Unified Ideographs. It consists of a set of principles and procedures on a number of items relevant to the preparation, submission and development of repertoires of CJK Unified Ideographs extensions for addition to the [ISO/IEC 10646](#) standard. Submitters should check the standard documents (including all the amendments and corrigenda) before preparing new submissions.

For any issue that is not explicitly covered in this document, the IRG will follow the Principles and Procedures of WG2¹ and other higher level directives.

1.1. Scope of IRG Work

The IRG works on CJK ideograph-related tasks under the supervision of WG2 (SC2 Resolution M20-07). The following is a list of current and completed IRG projects:

- a. CJK Unified Ideograph Repertoire and its extensions
- b. Kangxi Radicals and CJK Radical Supplements (completed)
- c. Production of Ideographic Description Sequence
- d. International Ideographs Core (IICore) (completed)
- e. CJK Strokes (completed)
- f. Update of CJK Unification Rules

Work on new IRG projects requires the approval of WG2, and preparation of relevant documents for such approval is required before the IRG can officially launch any new projects.

1.2. Scope of this Document

The following sections are dedicated to the standardization of CJK Unified Ideographs, describing the set of principles and procedures to be applied in the development of new extensions to the CJK Unified Ideograph Repertoire as specified under work item a. in Section 1.1. In addition, the maintenance of the IRG website and registration procedure of IRG documents are detailed in Sections 5 and 6 respectively.

This document does not cover other IRG work items listed in Section 1.1. Standardizing CJK Compatibility Ideographs maintained in UCS for the purpose of round-trip integrity with other standards is out of the IRG scope. However, CJK compatibility characters submitted to WG2 must be reviewed by the IRG to avoid potential problems. For the handling of mis-unification and duplicate ideographs, Annexes I and J of WG2 Principles and Procedures attached to this document should be referenced.

2. Development of CJK Unified Ideographs

All new extension work must be approved by WG2 before the actual consolidation and review can be formally carried out. There are no fixed rules for initiating a new extension. The IRG can initiate a call for proposals once its current collection is near completion. Any member body, international consortium, or individual expert can initiate a new extension by submitting a proposal which states the need of a required repertoire. Submission of such a proposal must follow the principles and procedures stated in this document. The IRG will vet and confirm if the proposal is within its scope of work.

Taking into consideration (1) the urgency and justifications of the proposal, (2) the proposed repertoire size, and (3) its current workload, the IRG may take one of the following actions:

- a. Endorse the proposal and submit it to WG2 for approval as an urgently needed repertoire².
- b. Invite other member bodies to submit characters of similar nature so as to estimate the real workload before submitting the proposal to WG2 for endorsement.
- c. Accept the proposal as a contribution to an ongoing IRG work item.
- d. Reject the proposal with justifications. A rejected proposal may be revised and re-submitted to the IRG.

¹ <http://std.dkuug.dk/jtc1/sc2/wg2/docs/principles.html>

² See Annex C for Guidelines on Urgently Needed Characters.

2.1. Principles on Identification of CJK Unified Ideographs

2.1.1. Principles on Encoding

Ideographs that have the same abstract shape are unified under the unification rules (Annex S of ISO/IEC 10646) and assigned a single character code. A CJK ideographic character can take many actual forms depending on the writing style adopted. Examples of common writing styles include Song style and Ming style as typical print forms, Kai style as a handwritten form, and Cao style as a cursive form. Stylistically different forms of the same character may involve different numbers or different types of strokes or components, which may in turn affect identification of the abstract shape of the character. In order to reach a common ground for identifying abstract shapes to be encoded as distinct CJK Unified Ideographs, the IRG only accepts submissions using a print form of glyphs (usually Song style or Ming style). Other styles of writing are generally not accepted unless an approved transcription normalization specification is accepted by the IRG.

2.1.2. Unification Procedure of CJK Ideographs

Standard print forms of CJK ideographs are constructed with a combination of known components or stroke types. Many can be broken down into two components - a radical chosen to classify the character in dictionaries and possibly reflect the meaning of the character, and a phonetic component which represents the pronunciation of the character. Basically, two submitted print forms of glyphs with different radicals are distinct characters even if they have the same phonetic component, such as “嘆” (U+5606) and “歎” (U+6B4E). For non-trivial cases, further shape analysis must be conducted. Similar glyphs should be decomposed into radicals, components or stroke types and evaluated by following the unification procedure described in Annex S of ISO/IEC 10646.

2.1.3. Non-cognate Rule

Ideographs with different glyph shapes that are unrelated in historical derivation (non-cognate characters) are not unified no matter how similar their glyph shapes may be. The following gives examples of semantically different characters with very similar glyphs. They are considered to have different abstract shapes because they are non-cognate.

“戌”(U+620C) and “戌”(U+620D) differ only in rotated strokes or dots (S.1.5 a).

“干”(U+4E8E) and “干”(U+5E72) differ only in folding back at the stroke termination (S.1.5 f).

Because shape analysis alone may not tell non-cognateness or semantic differences, it is the submitter's responsibility to provide information and supporting evidence in order to invoke the non-cognate rule.

2.1.4. Maintaining Up-to-date Unification/Non-unification Examples

In Annex S, unification/non-unification examples are summarized from past practice and the lists are not exhaustive. If there is ambiguity in applying the unification/non-unification rules, the IRG must first have a formal discussion for agreement. In case there are worthy examples for recording, the IRG will add them to its lists of unification/non-unification examples maintained as the IRG working document series (IWDS) on the IRG website. The lists will be reported to WG2 from time to time as an input for Annex S revisions. The detailed procedure of IWDS update is given in Annex E.

2.2. Principles on Submission of Ideographs to the IRG

2.2.1. Basic Rules of Submission and Required Data to be Submitted

The IRG accepts various types of submissions as specified below. Along with their submissions, the submitters are required to provide the necessary information for IRG's consideration.

- New Sources to Standardized Ideographs.** For submissions specifying new sources (such as an existing or a new national standard) to existing standardized ideographs, the new sources must be reviewed and approved by the IRG before submission to WG2. Sources and source references in the current ISO/IEC 10646 standard can be found in clause 23 of ISO/IEC 10646 Fourth Edition (2014-09-01). See also Annex D for an up-to-date IRG list of sources.
- New Sources to Working Sets.** For submissions specifying new sources to remaining characters in previous standardization stages, the new sources must be reviewed and approved by the IRG before they are incorporated by the IRG technical editor into the up-to-date IRG list of sources for the current IRG working sets.

- c. **New CJK Compatibility Ideographs (Vertical extension).** Please be aware that WG2 accepts new CJK Compatibility Ideographs only under very extreme circumstances due to the effects of normalization and the need to add standardized variation sequences to accommodate them. The preferred method of treating unifiable characters whose distinctions are deemed important is by registering them in a new or existing Ideographic Variation Database (IVD) collection as new Ideographic Variation Sequences (IVSes). See Section 2.2.1.g.

To add CJK Compatibility Ideographs, a submitter needs to supply the following information, which will be reviewed by the IRG before submission to WG2 to avoid possible problems of unification or dis-unification with other CJK Unified Ideographs.

- (1) Table showing the following data for each proposed CJK Compatibility Ideograph
 - a) UCS code position of the corresponding CJK Unified Ideograph
 - b) Glyph(s) of the corresponding CJK Unified Ideograph
 - c) Glyph of the CJK Compatibility Ideograph to be printed in the appropriate column of CJK Compatibility Ideographs Code Table
 - d) Source reference (for detailed format, see 2.2.1.d.(5)).
 - e) Evidence showing why the CJK Compatibility Ideograph needs to be added to UCS (e.g., a national standard showing two distinct code positions for two glyphs that are one and the same).
 - (2) TrueType font containing the glyph to be printed in the appropriate column of CJK Compatibility Ideographs Code Table (for detailed format, see 2.2.2.b.)
- d. **New CJK Unified Ideographs (Vertical extension).** All CJK Unified Ideograph submissions are subject to the following rules:
- (1) **Size for the Working Sets of an IRG Collection:** As all collections are defined by submitters according to their own criteria, the IRG does not impose a limit on the collection size. However, to rationalize the feasibility of a timely checking process and to achieve a high quality of work within a reasonably short period of time, the size of a collection or a part of an IRG collection, to be reviewed by IRG member bodies as a working set normally does not exceed 4,000 ideographs. Based on this principle, submitters should refrain from submitting more than 1,000 characters in each call for an IRG collection. Submitters may also be asked to divide their submissions into subsets to be processed in different working sets of an IRG collection. The guidelines for forming the working set are given in Annex L.
 - (2) **Pre-submission Unification Checking:** Submitters should be EXTREMELY CAREFUL *not to submit CJK Unified Ideographs that are already standardized or previously discussed* and recorded at IRG meetings. By the nature of ideographs, it is very difficult for IRG reviewers to find out all unifiable ideographs. Thus, it is important to achieve high quality at the time of submission. Submitters must make sure that the ideographs they submit do not fall into any of the following categories:
 - a) Ideographs already standardized in the ISO/IEC 10646 standard (including its amendments).
 - b) Ideographs currently in WG2's working drafts.
 - c) Ideographs currently in the IRG working sets including both M-set and D-set³.
 - d) Ideographs mis-unified or over-unified with ideographs in the current standard based on the lists maintained by the IRG in its working document series, namely IWDS_MUI and IWDS_NUC.
 - e) Ideographs from ancient documents that are rare and not in general use, along with variants from tombstone carvings that are not in circulation nor used in printed form, should have an appropriate base character identified through the use of authoritative dictionaries and other references, then be submitted as IVSes to be registered in a new or existing IVD collection. See Section 2.2.1g.

Low quality submissions may be rejected under the "5% Rule" defined in Section 2.2.5 below.

- (3) **Document Registration:** All submission documents should be registered as IRG documents with an IRG document number (IRGN). The file names should be in the form of:

IRGNnnnn_mmmm_pppp_sub_sss

where *nnnn* indicates an IRG document number assigned by the IRG Rapporteur, *mmmm* indicates the submitter's abbreviation (as listed in 2.2.1.d.(5), *pppp* indicates the collection

³ See Section 2.3.4 for the purposes of M-set and D-set.

year (such as 2015 for the 2015 collection), “sub” is a short hand for submission, and **sss** can be any submitter-designated indicator.

- (4) **Submission of Over-unified or Mis-unified Ideographs:** Submissions of ideographs that are found mis-unified or over-unified within the current standard should follow the principles in Annex I of WG2 Principles and Procedures. Lists of over-unified and mis-unified ideographs should be maintained by the IRG technical editor and made available for update in the IRG working document series (i.e. IWDS_NUC and IWDS_MUI) according to the maintenance procedure defined in Annex E of this document. For mis-unified non-cognate characters, requests can be made to add new code points for disunified characters.⁴
- (5) The following data items for each proposed ideograph must be submitted in CSV (Comma Separated Value) text format (in UTF-8) or Microsoft Excel file format:
- * Sequence number starting from 1 is required in the first column of each row.
 - a) **Source Reference** to indicate the source and the name of the glyph image for tracking. The source reference should begin with a member body abbreviation (G, H, J, K, KP, M, MY, T, UTC or V)⁵ or an international consortium abbreviation (U) followed by no more than 9 characters. It should contain only Latin capital letters and Arabic numbers to indicate the source. Numeric values to indicate the position in a specific source should be followed by a hyphen (“-”). The purpose of source references and an exhaustive list of source references accepted by ISO/IEC 10646 are provided in Section 23 of ISO/IEC 10646. See Annex D for details of member body/international consortium abbreviations.
 - b) **Glyph Image File Name.** The file name of each glyph image must be the same as the source reference with file extension of .bmp in bitmap format or .png in PNG format.
 - c) **Kangxi Radical Code** from 1 to 214⁶ with an additional .0 or .1 to indicate a traditional radical(0) or simplified radical(1). The selection of 0 or 1 is based on the radical’s glyph shape. The list of radicals with both traditional and simplified glyphs is given in Annex A.a.
 - d) **Stroke Count** of components other than the radical. In case of unified characters, the assignment of stroke count will be based on IRG agreed rules (ref. IRGN954AR and IRGN1105). In case of single source characters, this attribute will be assigned by the IRG Chief Editor following the actual shape.
 - e) **First Stroke** from 1 to 5 as listed in Annex K for components other than the radical. The IRG does not enforce a unified method of first stroke assignment as specified in IRGN954, IRGN954AR, and IRGN1105. It is however advisable for submitters to supply their assignment principles to the technical editor for spotting differences between different submissions. The final decision on first stroke selection rests with the technical editor for IRG editorial work. If the decision of the technical editor is different from that of the submitter, the submitter should be informed of the change.
 - f) **Flag to show whether the ideograph is traditional (0) or simplified (1).**
 - g) **Ideographic Description Sequence(IDS)** (ref. IRGN1183).
 - h) **Similar Ideographs** if available (identified by their code points in the standard in the form of U+xxxx). Enter “No” if no known variants; leave the column empty if not checked.
 - i) **References to evidence documents** including document names and other information. Submitters may supply additional information related to evidence submission and additional columns can be added as sub-items of i). For example, in addition to i) as the name of the original evidence document, submitters may include i1) for page number in the document, i2) for row number in that page, i3) to indicate position in that row, and i4) as the name of the JPG file showing the page of an evidence document where the character in question appears.
 - j) **kTotalStrokes** an integer indicating the total number of strokes of a character, including that of its radical. The IRG understands the possible ambiguity of strokes even in individual submissions. This attribute is requested by UTC of Unicode for the Unihan database to maintain locale-related data. The IRG will not check the data and takes no responsibility for its correctness.
 - k) **Optional Information** in text format can be included in additional columns starting

⁴ It should be noted that the source separation rule described in Annex S of the ISO/IEC 10646 is confined to coding standards listed in that section and is not applicable to new IRG submissions.

⁵ Member body abbreviations correspond to the source standard categories in Section 23 of ISO/IEC 10646 except **MY**.

⁶ The corresponding code range for Kangxi radicals in ISO/IEC 10646 is from U+2F00 to U+2FD5.

from k).

Some sample submissions are provided in Annex G for reference.

A blank form in Excel format is available for submitters' use as a separate document.

- e. **Existing CJK Compatibility Ideographs (Horizontal extension).** To add new source references to existing CJK Compatibility Ideographs, a submitter needs to supply the following information, which will be reviewed by the IRG before submission to WG2 to avoid possible problems.
- (1) Table showing the following data for each proposed horizontal extension of CJK Compatibility Ideographs
 - a) Code position of the existing UCS CJK Compatibility Ideograph
 - b) Glyph(s) of the existing UCS CJK Compatibility Ideograph
 - c) Code position of the corresponding UCS CJK Unified Ideograph
 - d) Glyph(s) of the corresponding UCS CJK Unified Ideograph
 - e) Glyph of the Compatibility Ideograph in the source reference
 - f) Glyph of the Compatibility Ideograph to be printed in the appropriate column of CJK Compatibility Ideographs Code Table
 - g) New source reference (for detailed format, see 2.2.1.d.(5))
 - h) Evidence showing why a new source reference for the CJK Compatibility Ideograph needs to be added to UCS (e.g. a national standard showing two distinct code positions for two glyphs that are one and the same)
 - (2) TrueType font containing the glyph to be printed in the appropriate column of CJK Compatibility Ideographs Code Table (for detailed format, see 2.2.2.b.)
- f. **Existing CJK Unified Ideographs (Horizontal extension).** To add new source references to existing CJK Unified Ideographs, a submitter needs to supply the following information. These characters must be reviewed by the IRG before submission to WG2 to avoid possible problems.
- (1) Table showing the following data for each proposed horizontal extension of CJK Unified Ideographs
 - a) Code position of the existing UCS CJK Unified Ideograph
 - b) Glyph(s) of the existing UCS CJK Unified Ideograph
 - c) Glyph of the CJK Unified Ideograph to be printed in the appropriate column of CJK Unified Ideographs Code Table
 - d) New source reference (for detailed format, see 2.2.1.d.(5).a)
 - e) Evidence showing why a new source reference for the CJK Unified Ideograph needs to be added to UCS (e.g., a national standard showing the relevant glyph)
 - (2) TrueType font containing the glyph to be printed in the appropriate column of CJK Unified Ideographs Code Table (for detailed format, see 2.2.2.b.)
- g. **Ideographic Variation Database (IVD).** For unifiable characters, which may be present in an IRG working set and identified as such, members are strongly encouraged to register them as IVSes in a new or existing IVD collection according to the procedures described in Unicode Technical Standard #37(UTS #37) (Unicode Ideographic Variation Database). If IRG approves and authorizes the registration of the IVSes in a new or an existing IVD collection, registration fee will not be charged⁷.

2.2.2. Required Font to be Submitted

- a. **Glyph Image:** Each proposed ideograph must be accompanied by a corresponding 128 x 128 bitmap file in Song or Ming style. The file name should be the same as the source reference (defined in Section 2.2.1.d.(5) with .bmp as its file extension).
- b. **TrueType Font (optional):** TrueType font availability is highly recommended although not necessary. Font specification can be found under point 5 of A.1. – Submitter's Responsibilities in Annex A of the Principles and Procedures of WG2. The IRG at certain stage of project development will set a deadline for TrueType font submission.

2.2.3. Required Evidence to be Submitted

Supporting Evidence: Evidence of the proposed glyph shape, its usage and context with pronunciation(s), meaning(s), etc. should be supplied to convince the IRG that it is actually in use or non-cognate with other similar ideographs. The appearance of a character as a head entry in a

⁷ IRG does not consider it appropriate to maintain an IRG unified IVD collection. However, IRG is willing to help review individual submissions to UTC.

dictionary is generally considered evidence of actual use if the dictionary is listed in Annex D or is otherwise accepted by IRG as an authoritative source.

- a. Evidence for each character must be supplied as scanned images. The provision of evidence on character usage including uses for personal names should not be exempted. A declaration for character use without accompanying evidence is generally not acceptable. Considering privacy issues, the IRG has suggested some compromised provisions. Details are given in Annex G.3.

Note: To support e-government related initiatives, the IRG may at its discretion accept submissions of characters that are used in computer systems administered by government bodies for public service with wide access by government agencies and citizens. Factors considered for such acceptance are further elaborated in Annex G.4.

- b. **Questionable Characters** (optional): For candidate ideographs with possible unification questions, in addition to listing the possible unifiable characters as required in 2.2.1.d.(5h), submitters are encouraged to provide for review detailed evidence of use from authoritative sources, and evidence showing their relationship to other standardized ideographs or variants having similar shape or meaning. Characters with this information are not counted as problem characters for quality assurance assessment given in 2.2.5.
- **Avoidance of Derived Simplified Ideographs:** To avoid encoding derived simplified characters that are not in actual use, submissions of derived simplified ideographs require actual usage evidence. Providing only their corresponding traditional ideographs will not be considered as producing usage evidence. Derived simplified characters from a dictionary as a source should not be used as the sole evidence of actual use unless the dictionary is an IRG-accepted authoritative dictionary.

2.2.4. Required Summary Form to be Submitted

Each submission for an ideograph proposal should be accompanied by a duly completed "Proposal Summary Form for Addition of CJK Unified Ideographs to the Repertoire of ISO/IEC 10646" (see **Annex F**).

2.2.5. Quality Assurance: The 5% Rule

For all character encoding standards, a common general principle is to encode the same character once and only once. Before any submission, it is the submitter's responsibility to filter out ideographs that are already in the ISO/IEC 10646 international coding standard:

- the published standard,
- any of its published amendments,
- any of its amendments under ballot in JTC1/SC2, or
- any of the working sets of the IRG.

In assessing the suitability of a proposed ideograph for encoding, the IRG will evaluate the credibility and quality of the submitter's proposal. If the IRG finds more than 5% of the submitter's source set are duplicates of characters in the above mentioned proposals during the IRG review process, the whole submission will be removed from the subsequent IRG working drafts for that particular IRG project. However, the 5% rule does not apply if the submitter explicitly raises questions about unification/dis-unification for concrete cases in the proposal of characters.

It should be noted that the 5% rule is a general yardstick to remind submitters to adhere to IRG submission requirements and do a good screening job before submission to reduce the workload of member bodies for quality review. In practice, most submissions should have problems within the 1% range. In this regard, submitters should not interpret the rule as submissions with problems within the 5% range will definitely be accepted. The IRG has the right to review the problem cases and decide not to accept a submission even if it has problems within the 5% range (especially when the figure is very close to 5%).

2.3. Principles on Production of IRG Working Drafts

After the IRG accepts submissions based on principles specified in Section 2.2, and follows the guidelines to form working sets of the current collection, the development process of the current working set begins⁸. The IRG technical editor will first produce a set of IRG working drafts.

2.3.1. Principles on Submitted Ideographs

- a. All the original ideograph submissions, including submissions of glyphs, IDS, radicals, stroke counts and evidence, must have registered IRG document numbers.
- b. If any required information is missing, the IRG chief editor or technical editor can ask for additional information from the submitter. Without timely supply of such information, the submission may be rejected by the technical editor in producing the working drafts.

2.3.2. Principles on Assignment of Serial Numbers

- a. The IRG technical editor will consolidate and sort the submitted ideographs in accordance with Annex A of this document.
- b. A unique *serial number* will be assigned to each submitted ideograph after consolidation. The serial numbers must be unique throughout the standardization process. They must not be changed, re-set or re-assigned unless there is an agreed dis-unification during the process. This principle allows easy reference to past discussions. In case of a split, one ideograph will keep the original serial number and the other will be assigned a new serial number.
- c. If ideographs submitted by different submitters are obviously unifiable, such ideographs may be unified and assigned the same serial number by the IRG technical editor.

2.3.3. Principles on Machine-checking of IDS of Submitted Ideographs

- a. The IRG technical editor will check the submitted IDS with existing IDS data to detect possible unifiable or duplicate ideographs.
- b. Machine checking sometimes detects obviously non-unifiable pairs. In such cases, when detected, they will be noted and assigned with different serial numbers before proceeding to the next stage.
- c. The IDS checking algorithm would satisfy the requirements described in Annex B.

2.3.4. Production of IRG Working Drafts

- a. **Division of Character Subsets:** By the result of IDS checking, submitted ideographs will be grouped into the following two subsets:
 - (1) **M-set (main set):** for ideographs with proper IDS and found not to be unifiable with current standardized ideographs or previously discussed ideographs with proper IDS.
 - (2) **D-set (discussion set):** for ideographs with missing, incomplete, or inconclusive IDS, or ideographs of which the attribute data have been questioned by any member body during a review process, or ideographs that might be unifiable with standardized or previously discussed ideographs. Ideographs with missing or incomplete IDS will be commented as such, and checked intensively through manual checking. Ideographs that might be unifiable with standardized or previously discussed ideographs will also be commented as such, and their suitability for unification must be manually checked. Dis-unification must be supported by evidence.
- b. **Naming of Working Drafts:** The file name should follow the format of "IRGNnnnnVX[XXX]" where *nnnn* is the IRG assigned document number and *X* is the version number. No spaces are allowed. But, the use of underscore "_" and period "." for separation is permissible. Examples of version numbers are "ExtFV1.0", "V1.0Draft", etc.
- c. **Glyph Images:** An archive of consolidated glyph images will be produced. Each image should be in the size of 128 x 128 pixels with file name using the source reference and the extension .bmp.
- d. **Addition of Characters:** No ideographs should be added to the working sets once the development process begins.
- e. **Alteration of Characters:** Alteration of characters is generally not allowed because it indicates instability and may have impact on other characters in the collection. However, submitters may submit proposals of minor alterations of characters with justifications at the final stage or with explicit approval from the IRG as long as the altered glyphs are unifiable with the original characters. A change of glyph beyond the Annex S unification criteria is considered to be an addition of a new character and is NOT acceptable during the development process. The submitter of any alteration proposal must provide the results of thorough checks and

⁸ In case of multiple working sets in a collection, the review will be conducted for one working set at a time. Once a working set is completed and submitted to WG2, the review of the next working set will start. The process repeats until all working sets are finished in sequence.

verification showing that the alteration does not affect other characters in existing standards and working sets. The IRG, based on its evaluation, may decide to accept the alteration, reject the proposal or request the removal of such a character by the submitter. If the submitter finds that the glyph of a character is wrong at any working stages, the character will be rejected by the IRG and should be withdrawn by the submitter.

- f. After consolidation, the IRG chief editor and technical editor may ask member bodies to review M-set and D-set based on an agreed IRG review schedule and task division.

2.4. Principles on Reviewing IRG Working Drafts

If the IRG instructs member bodies to review the working drafts (different portions may be assigned to different member bodies), member bodies' editors should review it according to the agreed schedule. They should follow the principles set out below during the review process.

2.4.1. General Principles on Reviews

- a. Each member body should check the ideographs of the current working set assigned by the IRG chief editor and technical editor for the following issues:
 - (1) Correctness of Kangxi radical, Kangxi index, stroke count, first stroke and IDS.
 - (2) Correctness and quality of glyphs and source information if necessary.
 - (3) Presence of duplicate or unifiable ideographs based on Annex S guidelines.
 - (4) Consistency of submitted characters with the submitted evidence and documentary proof.
- b. When any data of an ideograph, including IDS, Kangxi radical, or stroke count are found to be incorrect, the ideograph should be moved from M-set to D-set as its standing data are no longer valid. Until the ideograph is confirmed to be unique by manual checking (procedure described in Section 2.4.2. below), it should not be moved back to M-set.

2.4.2. Principles on Manual Checking

- a. **Duplication and Unification:** For D-set ideographs, member bodies should ensure that they are not duplicates of or unifiable with any ideographs in the standard, working set(s) submitted to WG2, or in the current working set .
- b. **Radical Checking:** Assurance is done by enumerating all possible radicals of a target ideograph and looking for any duplicate or unifiable ideographs in the range of ± 2 stroke counts of ideographs in the standard, working set(s) submitted to WG2, and current working set. For example, “聞” may have the radical of “門” with 6 strokes for the remaining component, or the radical of “耳” with 8 strokes for the remaining component. In such a case, checking the standard, working set(s) submitted to WG2, and current working set for ideographs with radical of “門” and 4-8 strokes, or ideographs with radical of “耳” and 6-10 strokes manually can better assure that the ideograph does not have duplicate or unifiable ideographs.
- c. **Recording of Review Results:** The checking work should be recorded in the review comments as “Checked against all ideographs in the standard, working set(s) submitted to WG2, and current working set with radical X and stroke count of Y ± 2 .”

2.4.3. Submission of Possibly Unifiable Ideographs

- a. **Preparation of Comments:** Member bodies should prepare comments and feedback quoting the assigned serial numbers of the ideographs in question. The guidelines on comments are described in Section 4 of this document. Comment files should be tabulated in CSV text format, Microsoft Excel, or Word file format. All comment files must have pre-assigned IRG document numbers.
- b. **Additional Evidence and Arguments:** For each proposed ideograph in the D-set that has been questioned for possible unification, the submitter should prepare arguments with further evidence of its use and documentary proof (for example, from dictionaries, legal documents or other publications) showing that it is not unifiable with any standardized ideograph or ideograph proposed in the same or another working draft. When submitters disagree with a suggested unification, it is insufficient to simply point out that there is no unifiable component variations (UCV) examples. The UCV list and other documents in the same IWDS are working documents subject to ongoing update as a result of IRG Working Set reviews. In other words, “No case in UCV list” is no longer a sufficient reason for dis-unification. The IRG requests submitters to also provide unification and dis-unification examples from published versions of the standard as well as those accepted for publication. The additional information will help the IRG to determine whether the ideographs in question should be dis-unified or unified (which may result in additional UCVs or other related documents).
- c. **Submission Deadline:** Each member body should send feedback comments at least two months before the next IRG meeting. The IRG chief editor and technical editor will consolidate them and register the results as IRG documents one month before the next IRG meeting.

- d. **Written Responses from Submitters:** Submitters should examine the consolidated comments on their respective characters and send the IRG chief editor and technical editor a written document containing their responses to the comments together with additional evidence at least one week before the next IRG meeting.
- e. **Rejection:** Questioned ideographs with no counter arguments in support of dis-unification supplied to the IRG meeting will be automatically marked as unified.
- f. **Revised font:** In case of a glyph mismatched to evidence or mismatched to normalization for consistency, the submitter needs to provide a revised font to IRG for review.

2.5. Principles on Discussions at IRG Meetings

2.5.1. Document-based Discussion

For efficient and smooth work, all discussion items and evidence must be presented as registered IRG documents before the commencement of an IRG meeting. Items or evidence that are not contained in a registered IRG document will not be discussed or treated as evidence during IRG meetings. Discussions on evidence or items raised after the commencement of an IRG meeting may be postponed to the next IRG meeting if any member body requests longer time to examine such evidence or items.

2.5.2. Discussion Procedure

Discussions will be based on the review comments on the current working set. For unification issues, the submitters should present evidence documents showing that the suspected unifiable ideographs are distinctively used as non-cognate characters in the same region, or that they cannot be unified in accordance with Annex S. When IRG member bodies have reached a consensus that two ideographs are unifiable, the submitter concerned should take one of the following actions, and the decision must be recorded.

- a. Withdraw the now-unified ideograph and add a new source reference to the existing standardized or working set ideograph. This is particularly important if the existing standardized or working set ideograph to which it is unified does not yet have an assigned source reference that corresponds to the member body that submitted the now-unified ideograph.
- b. Register the now-unified ideograph in a new or an existing IVD collection as a new IVS, particularly if the existing standardized or working set ideograph to which it is unified already has an assigned source reference that corresponds to the member body that submitted the now-unified ideograph.

When characters are reviewed by different people, different choices of Kangxi radical, stroke count or first stroke code are possible for the same ideograph. IRG member bodies should agree on the most appropriate ones based on the commonest abstract shape of the specific glyph. When the Kangxi radical or stroke count of an ideograph is found to be incorrect, the ideograph will be moved to D-set pending another manual review to prevent any unification errors caused by not having conducted the review with ideographs having the correct Kangxi radical or stroke count.

Guidelines on typical comments and resolutions are given in Section 4 of this document.

2.5.3. Recording of Discussions

Comments, rationales, and decisions must be recorded for each ideograph reviewed in a tabular format for reference and checking.

2.5.4. Time and Quality Management

Before a discussion begins, the number of ideographs under review will be counted and the schedule will be estimated based on it. During the discussion, the number of comments reviewed per hour will be noted and the schedule will be adjusted according to the progress (Note: It is recognized that some comments may take longer than others to discuss and resolve). If the comments cannot be handled in one IRG meeting, they may be partitioned and resolved in subsequent IRG meetings. Due to the limited time CJK Editorial Group has to deal with individual characters during an IRG meeting, member bodies can use emails to discuss and reach agreement on simple, straightforward cases before and after an IRG meeting.

2.6. Principles on Submission of Ideographs to WG2

2.6.1. Checking of Stabilized M-Set

- a. Once M-set is consolidated and stabilized, the ideographs in M-set will be checked intensively as a complete set at least once to ensure data and glyph integrity.
- b. Approval by a majority vote of IRG member bodies is needed before the set can be prepared for WG2 submission.

2.6.2. Preparation for WG2 Submission

After the approval by the IRG, the IRG technical editor will prepare the proposal to be forwarded to WG2. The preparation includes the following:

- a. Sort the final stable M-set ideographs by the sorting algorithm described in Annex A.
- b. Assign provisional UCS code positions to the sorted M-set ideographs (with agreement from the ISO/IEC 10646 project editor on block assignment).
- c. Make available the TrueType font for each submitter with assigned provisional UCS code positions (fonts have to be available in accordance with the requirement stated in point 5 of A.1. – Submitter's Responsibilities in Annex A of WG2 Principles and Procedures).
 - (1) Each submitter is encouraged to prepare and submit its own font for best font quality.
 - (2) If a submitter has difficulty in creating the font, other member bodies or the IRG technical editor may help create the font. In this case, the glyph style of the submitter must be respected.
 - (3) If the submitter cannot provide the TrueType font by this time, its collection will be withdrawn from M-set.
- d. Prepare a list of source references.
- e. Produce a packed Multi-column Ideograph Chart using the TrueType fonts.

The IRG will conduct at least one round of review of the proposal and the chart generated using TrueType font before submission to WG2.

3. Procedures

This section describes the basic development procedure of CJK Unified Ideograph extensions. The ultimate purpose of the procedure is to realize the production of high quality CJK Unified Ideograph sets in an efficient manner.

The basic development procedure described in this section consists of 8 stages, and it may take two to three years to create a high quality ideograph set for standardization.

3.1. Call for Submission

- a. When a member body or an international consortium requests a new project for CJK Unified Ideograph extension or the IRG's current collection is near completion. The IRG may decide at an IRG meeting to call for submission of new ideographs to form a new collection. The IRG will specify the deadline for submission.
- b. The IRG will give a name to the new collection using the year of the call (in four-digit format)⁹.
- c. Each member body/international consortium with proposed ideographs must submit the ideographs before the specified deadline with the required data described in Section 2 of this document.
- d. Submitters must ensure that the ideographs are submitted with all the required information. If only minor problems are encountered, such as some required information is found missing or misplaced, the IRG chief editor or technical editor may ask the submitter to re-submit the information or supply additional information. Otherwise, the submission may be rejected because consolidation with other submissions cannot be carried out.
- e. An initial review of all submissions for a new collection will be done during an IRG meeting to estimate the size of the collection. The IRG will use the guidelines given in Annex L to estimate the number of working sets for the collection. If multiple working sets are deemed necessary, the IRG meeting will determine how the collection will be split so that the IRG can work on one working set at a time. The decision on the number of working sets may be revised after the review of the first consolidation in an IRG meeting as stated in 3.4.f.

⁹ The first IRG collection using this naming convention is IRG Collection 2015.

3.2. Consolidation and Grouping of Submitted Ideographs

Consolidation of submissions is normally done between IRG meetings. The consolidation involves the following tasks:

- a. The IRG technical editor will sort and assign *serial numbers* to submitted ideographs as described in Section 2.3.2.
- b. After serial numbers have been assigned, submitted ideographs must undergo IDS checking to detect any duplication and unification. Based on the result of IDS checking as described in Section 2.3.3, submitted ideographs will be grouped into M-set and D-set as described in Section 2.3.4.
- c. After consolidation, the working drafts will be assigned an IRG document number with a version number. They will be distributed to member bodies' editors and made available on the official IRG website so that any other experts can have access to them. The IRG chief editor and technical editor may assign member bodies' editors to check M-set and D-set ideographs for either the entire working set or certain portions of it depending on their reasonable estimation of the workload.

3.3. First Checking Stage

This stage, which is between IRG meetings, involves the following tasks:

- a. Each member body's editor must check the assigned M-set and D-set for data integrity, correctness, missing data and duplication. Checking for unification is not mandatory, but desirable. Typical review comment examples for each set are provided in Section 4.
- b. Member bodies must submit their comments in registered IRG documents to the IRG chief editor and technical editor at least two months before the next IRG meeting or according to the IRG approved working schedule.
- c. The IRG chief editor and technical editor will consolidate the comments and produce a registered IRG document for circulation and discussion at least one month before the next IRG meeting or according to the IRG approved working schedule.
- d. Submitters and outside experts are encouraged to prepare and submit supplementary documents (with IRG document numbers) so that they can be discussed at the next IRG meeting.

3.4. First Discussion and Conclusion Stage

This stage, which is during an IRG meeting, involves the following tasks:

- a. Member bodies and participating experts should review the comments which are officially submitted before the meeting with assigned IRG document numbers. The editorial group must reach conclusion for each commented ideograph in writing. Guidelines for typical conclusions are provided in Section 4.
- b. All the conclusions must be agreed and endorsed by the IRG plenary in its resolutions. As a result of the resolutions, some ideographs may be removed or moved between M-set and D-Set.
- c. The IRG technical editor will create a new M-set and D-set one month after the IRG meeting, and register them as IRG documents with version information.
- d. If more than 5% of the ideographs submitted by a specific submitter are removed as a result of duplication or unification with existing standardized ideographs, the entire submission of this submitter will be removed to ensure high quality of the project. This is known as the 5% rule described in Section 2.2.5 above.
- e. If new unification or non-unification cases or rules are agreed upon, such decisions must be recorded in a separate editorial report document. The IRG should also instruct the IWDS editor to modify and update the IWDS according to the guideline set out in Annex E of this document. This update will be reviewed and confirmed in the following IRG meeting so that it can be used in all future work. The 5% rule will not be applicable to unifications based on newly agreed unification rules.
- f. If decision on the number of working sets is not made in 3.1.e when the collection is first submitted, the IRG will review the size of the collection and determine the number of working sets at this stage. The working sets will go through the review process one at a time from 3.2 to 3.8 until all working sets are completed.

3.5. Subsequent Checking Stage

This stage, which is between IRG meetings, involves the following tasks:

- a. Each member body's editor must check the newly created M-set and D-set for correctness and duplication.
- b. Member bodies should submit their comments in registered IRG documents to the IRG chief editor and technical editor at least two months before the next IRG meeting or according to the IRG approved working schedule.
- c. The IRG chief editor and technical editor will consolidate the comments and produce a registered IRG document for circulation and discussion at least one month before the next IRG meeting or according to the IRG approved working schedule.
- d. Submitters and outside experts are encouraged to prepare and submit supplementary documents to facilitate discussion during the next IRG meeting.

3.6. Subsequent Consolidation and Conclusion Stage

This stage, which is during an IRG meeting, involves the following tasks:

- a. Member bodies must review the comments and draw conclusion for each ideograph. Typical comment and conclusion examples for each set are provided in Section 4.
- b. All the conclusions must be agreed and endorsed by the IRG plenary in its resolutions. As a result of the resolutions, some ideographs may be removed or moved between M-set and D-set.
- c. The IRG technical editor will create a new M-set and D-set one month after the IRG meeting, and produce a registered IRG document.
- d. If more than 5% of the ideographs submitted by a specific submitter are removed as a result of duplication or unification with existing standardized ideographs, the entire submission of this submitter will be removed to ensure high quality of the project. This rule will not be applicable to new unifications based on rules added after the first checking stage.

3.7. Final Checking Stage

This stage, which is between IRG meetings, involves the following tasks:

- a. All member bodies' editors are requested to check M-set intensively based on comments and conclusions made at all previous stages. At the final checking stage, no ideographs are allowed to be moved from D-Set to M-Set although ideographs in the M-set can still be moved to D-set if problems are found.
- b. Member bodies' editors must submit their comments in registered IRG documents to the IRG chief editor and technical editor at least two months before the next IRG meeting.
- c. The IRG chief editor and technical editor will consolidate the comments and produce a registered IRG document for circulation and discussion at least one month before the next IRG meeting so that member bodies' editors can have time to review them before the next IRG meeting.

3.8. Approval and Submission to WG2

This stage, which is during an IRG meeting, involves the following tasks:

- a. Member bodies should review the comments on M-set and reach conclusion for each ideograph.
- b. If there is no positive decision on an M-set ideograph, it will be moved to D-set. Again, no character will be moved from D-set to M-set at this stage. Ideographs may only be moved from M-set to D-set if problems are found.
- c. With the approval of the majority of IRG member bodies, M-set is considered frozen as the new ideograph extension set to be submitted to WG2. The IRG technical editor will prepare the submission in accordance with Section 2.6 of this document.

Once M-set is completed for submission to WG2, records of characters in the D-set will no longer be maintained by the IRG. Characters remained in the D-set can be re-submitted in future extensions if pending problems are solved.

4. Guidelines for Comments and Resolutions on Working Sets

Generally speaking, reviewers should put down their comments for any problems they want to alert other reviewers. For comments related to glyph shape, the relevant component(s) of the problem glyph

and the referenced glyph(s) should be marked in red circles/boxes in the comment files. Similarly, for comments concerning identical or different components of two or more ideographs, the corresponding components should be indicated in red circles/boxes in the comment files.

All comments must be accompanied with date (in YY-MM-DD format) and member body/international consortium abbreviation (G, H, J, K, KP, M, MY, T, U, V or Z). All conclusions must be dated.

4.1. Guidelines for M-Set

The ultimate target of M-set is a standardized ideograph set. As such, it must be carefully examined. If any suspicious characters are found, they will be moved to D-set or removed from the current working set altogether.

For comments on glyph shape, the relevant components of the ideographs should be marked in red circles/boxes in the comment file as shown below.

201C3		Wrong Glyph	T glyph seems wrong: 行 in T glyph
-------	--	-------------	-----------------------------------

Similarly, for comments concerning identical or different components of two or more ideographs, the corresponding components should be marked in red circles/boxes in the comment file as shown below.

2010D		Glyph design	The T-glyph is different from the KX Dictionary glyph.
-------	--	--------------	--

The table below gives examples of review comments and possible actions associated with these problems:

Possible Comment by a Reviewer	Possible Resolution
Wrong or Missing Glyph	<ul style="list-style-type: none"> The wrong glyph is corrected, or the missing glyph supplied. The ideograph will be moved to D-set for manual checking.
Wrong Kangxi radical / stroke count / first stroke	<ul style="list-style-type: none"> Data will be corrected and the ideograph will be moved to D-set for further manual checking.
Wrong IDS	<ul style="list-style-type: none"> IDS will be corrected and the character will be moved to D-set for checking by the IDS checker. Move to D-set (in case IDS cannot be corrected).
May be unifiable with U+xxxxx (standardized ideograph)	<ul style="list-style-type: none"> Unified with U+xxxxx and the submitter will request a new source reference to U+xxxxx. Unified with U+xxxxx and the submitter will request that this character be treated as a Compatibility Ideograph. Unified to U+xxxxx and this entry will be removed. (May consider to register it as IVS.) Not unifiable.
May be unifiable with xxxx (M-set ideograph)	<ul style="list-style-type: none"> Unified with xxxx and this source reference will be attached to xxxx. Unified with xxxx and the submitter may consider registering it as a Compatibility Ideograph Character or IVS. Not unifiable.

4.2. Guidelines for D-Set

Ideographs in D-Set are either the ones that cannot be checked automatically by the IDS checking algorithm or the ones whose attribute data have been questioned by member bodies or whose unification with other ideographs in the standard, working set(s) submitted to WG2 or current working

set have been proposed. For those ideographs that cannot be machine-checked by IDS matching, at least two non-submitter member bodies must check them manually to ensure that they are not unifiable with any ideographs in the standard, working set(s) submitted to WG2, or current working set. For those ideographs that might be unifiable with other ideographs, the submitters are requested to prepare arguments and evidence to show that such ideographs should be separately encoded.

Possible Comment by IDS Checker	Possible Conclusion
<ul style="list-style-type: none"> ● Incomplete IDS ● IDS with extra character ● Component is not an ideograph 	<ul style="list-style-type: none"> ● IDS will be corrected and the character will be moved to M-set when next IDS-checking is done. ● Proper IDS cannot be generated and manual checking is needed.
Possible Comment by a Reviewer	Possible Conclusion
<ul style="list-style-type: none"> ● Wrong Kangxi radical ● Wrong stroke count ● Wrong first stroke 	<ul style="list-style-type: none"> ● Data will be corrected. ● Proposal to correct data is not accepted, as it is an ambiguous case and the IRG agrees that the previous choice of XX is more appropriate.
● Wrong IDS	<ul style="list-style-type: none"> ● IDS will be corrected and checked by the IDS checker again. ● Correct IDS cannot be generated and manual checking is needed.
May be unifiable with U+xxxxx (standardized ideograph)	<ul style="list-style-type: none"> ● Unified with U+xxxxx and a new source will be added to U+xxxxx. The new candidate entry should be deleted. ● Not unifiable, as shown by the evidence /IRGN xxxx. Move to M-set.
May be unifiable with xxxx (M-set or D-set ideograph)	<ul style="list-style-type: none"> ● Unified with xxxx in M-set and a new source will be added to xxxx. The new candidate entry should be deleted from D-Set. ● Unified with xxxx in D-Set and a new source will be added to xxxx. The new candidate entry should be removed from D-Set. ● Not unifiable, as shown by the evidence /IRGN xxxx. Move to M-set.
Checked against all ideographs in the standard, working set(s) submitted to WG2 and current working set with radical X and stroke count of Y±2 for characters that cannot be described by IDS for automatic checking.	<ul style="list-style-type: none"> ● Move to M-set, as two non-submitter member bodies (XX and YY) confirmed that this ideograph is not unifiable with any existing ideographs in the standard, working set(s) submitted to WG2, or current working set. ● Checking against ideographs with radical X may not be enough. This ideograph will also be checked against ideographs with radical Z.

5. IRG Website

The IRG maintains its own website at <http://www.cse.cuhk.edu.hk/~irg/>, hosted by the Department of Computer Science and Engineering at The Chinese University of Hong Kong. IRG meeting notices, resolutions, document register, documents and standing documents are made available on this site. Hyperlinks to WG2 websites are provided for member bodies' easy access. For faster retrieval of documents and searching, documents should not be compressed as far as possible and the site search engine window should be made available. Documents larger than 4MB must be split into multiple files for easy uploading, downloading and searching. The compressed files can be in either WinZip format with .zip extension or RAR format with .rar extension.

6. IRG Document Registration

All documents to be formally discussed by the IRG must be registered with IRG document numbers assigned by the IRG Rapporteur and contain the submission date, title, name of the submitter or author, purpose (or summary), and the "IRG Ideographic Repertoire Submission Summary Form" (when applicable).

6.1. Registration Procedure

The following gives the registration procedure:

- a. **Request for Document Number:** All documents submitted to the IRG must be given a document number. The number is to be assigned by the IRG Rapporteur. The submitter should first contact the IRG Rapporteur for a document number with a document title. Once the document number is assigned, the information will be posted on the IRG website. Document numbers can be pre-assigned during IRG meetings for activities between IRG meetings.
- b. **Submission of Documents:** All registered documents must be submitted to the IRG Rapporteur. The submitted documents must contain an assigned IRG document number in text form (except files of pure tables to avoid interfering with the data presented in the table) so that searching can be supported. Note: Feedback to and comments on a given document will not be assigned a new document number. Rather, they will use the same document number with extensions to facilitate tracking for the same topic.
- c. **File size:** Documents larger than 4MB must be split into multiple files for easy uploading, downloading and searching. The compressed files can be in either zip format with .zip extension or RAR format with .rar extension. For files that are much larger than 4MB, the submitters should inform the IRG Rapporteur in advance. The IRG Rapporteur can, at his/her discretion, instruct the submitters to submit them as large files, which will be handled differently.
- d. **Posting of Documents:** Properly submitted documents are then posted by the IRG Rapporteur on the IRG website as official documents and the submitters will be notified by the IRG Rapporteur by email. The submitters should double check the posted documents upon receiving the emails to ensure that the intended documents are properly posted for viewing by the public. In case of a large file, the submitter must first provide a method (e.g., web download, ftp) for the IRG Rapporteur to obtain the file. The IRG Rapporteur will then post it on the IRG large-file posting sites and provide the link(s) on the IRG website for download.
- e. **Disqualified Documents:** Documents with certain basic information missing such as the submitter's name, title, purpose or files that are not in the appropriate size may be rejected by the IRG Rapporteur for posting. All other documents that fail to comply with the above registration process and the preliminary review by the IRG Rapporteur for basic information will not be treated as IRG documents. As such, issues contained in such documents will not be discussed by the IRG formally.
- f. **Document format:** Documents submitted by submitters should use the most commonly-used document format for easy reading by members on all platforms. Static documents should use PDF. Data files intended for consolidation, revision and processing can use other appropriate document formats depending on the nature of data, such as Microsoft Excel, CSV, plain text, or PNG.

6.2. Contact for IRG Document Registration

The current IRG Rapporteur is Prof. Qin LU and her contact information is as follows:

Professor Qin Lu
Department of Computing
The Hong Kong Polytechnic University
Hung Hom, Hong Kong
Tel. (852) 2766 7247
Fax. (852) 2774 0842
Email: csluqin@comp.polyu.edu.hk

Annex A: Sorting Algorithm of Ideographs

The IRG recognizes that the choice of radicals, the sequence of strokes, and the stroke counting methods are locale dependent. Submitters may have different preferences of character orders. However, for the convenience of IRG editorial work, the IRG must adopt a sorting order which may be different from the submitters' preferences. Thus the principles of sorting of ideographs given below are internal for IRG editing purposes only. Ideographs consolidated for unification review must be sorted according to the following order.

a. Kangxi Radical Order

Note: Ideographs with the simplified radicals listed below must be placed after ideographs with the corresponding traditional radicals.

Traditional Radicals		Simplified Radicals	
R090.0	爿	R090.1	冂
R120.0	糸	R120.1	纟
R147.0	見	R147.1	见
R149.0	言	R149.1	讠
R154.0	貝	R154.1	贝
R159.0	車	R159.1	车
R167.0	金	R167.1	钅
R168.0	長	R168.1	长
R169.0	門	R169.1	门
R178.0	韋	R178.1	韦
R181.0	貢	R181.1	页
R182.0	風	R182.1	风
R183.0	飛	R183.1	飞
R184.0	食	R184.1	饣
R187.0	馬	R187.1	马
R195.0	魚	R195.1	鱼
R196.0	鳥	R196.1	鸟
R197.0	齒	R197.1	齒
R199.0	麥	R199.1	麦
R205.0	鼈	R205.1	龟
R210.0	齊	R210.1	齐
R211.0	齒	R211.1	齿
R212.0	龍	R212.1	龙
R213.0	龜	R213.1	龟

b. Stroke Count

Note: Simplified characters must be placed after traditional characters within the same stroke-number group.

c. First Stroke

The technical editor will assign the first stroke based on IRGN954AR and IRGN1105. In case of previously unseen components, the technical editor will take the conventions of Kangxi for first stroke assignment without regard to the submitters' locale conventions.

Annex B: IDS Matching

B.1. Guidelines on Creation of IDS

Each member body should consult IRGN1183 on IDS. In addition to the Character Description Components (CDC) defined in IRGN1183, all CJK Unified Ideographs accepted by ISO/IEC 10646 in its amendments are also qualified as CDC in constructing IDS.

The use of “overlapping” Ideographic Description Characters (IDC) or more than four IDCs is considered to be “inappropriate” and may not be a subject of IDS comparison.

B.2. Requirements of IDS Matching

The IDS matching algorithm used by the IRG should support the following features:

1. Handling different split points.
(e.g. 𠂇 頃 and 𠂇 化頁 should be matched.)
2. Handling different split levels.
(e.g. 𠂇 悅 and 𠂇 采心 should be matched.)
3. Matching different glyphs of the same abstract shape.
(e.g. 𠂇 申 and 𠂇 示申 should be matched.)
4. Matching similar glyphs.
(e.g. 𠂇 小生 and 𠂇 小生 should be matched.)
5. Matching IDS with different orderings of overlapping IDC.
(e.g. 𠂇 三 | and 𠂇 | 三 should be matched.)
6. Matching unifiable IDC patterns.
(e.g. 𠂇 麥 禹 and 𠂇 麥 禹 should be matched.)
7. Handling any combinations of the above.
8. Detecting any inappropriate IDS, such as IDS being too long, IDS with non-ideographic CDC, or missing or extra CDC or IDC.

B.3. Limitation of IDS Matching

It should be noted that IDS matching cannot detect unification or duplication if a component cannot be encoded by an IDS, or if the glyph itself is very complex. IDS matching is done algorithmically. It is not versatile in detecting unifiable ideographs unless rules are explicitly given to the algorithm. Thus, it is not meant to be the replacement of manual checking. Rather, it is an assistive tool for quality assurance to identify duplication and known cases of unification. Therefore, it is very important for submitters to make sure that their submitted ideographs are not going to be unified with any standardized or previously discussed ideographs or working set ideographs.

Annex C: Urgently Needed Ideographs

C.1. Introduction

When a member body or an internationally recognized organization, consortium, or individual, as a submitter, demonstrates an urgent need for a small number of ideographs to be standardized for justifiable reasons, such as ideographs in a recently developed regional or national standard that must be implemented by a particular deadline, the IRG may submit the ideographs, independent of the current IRG working set to WG2. Each urgently needed submission will be treated as a separate urgently needed repertoire, and a submitter can have no more than one active urgently needed submission at a time. The process will be started only sparingly with demonstrated need.

C.2. Requirements

Each submission should include no more than 30 ideographs. Submissions of more than 30 characters will be accepted at the sole discretion of the IRG. A submitter of urgently needed ideographs must prepare the following:

- a. All the documents required for normal ideograph submissions.
- b. Justifications of the submission. A submission is deemed urgently needed only if the submitter demonstrates urgency or a rationale for rapid standardization. Evidence of current use is not in and of itself evidence of urgent need. The type of use also needs to be taken into account. For example, requirements of government, industry, science, or scholarship will generally be taken as evidence of urgent need.
- c. A document that indicates whether, among the submitted urgently needed ideographs, there are any ideographs that can be unified with ideographs in the current IRG working set in addition to those in the standard or its amendments. When a particular urgently needed repertoire is accepted by WG2, any unifiable ideographs in the current working set will be removed as explained in C.3 below.
- d. For the rest of the submitted urgently needed ideographs, the document must prove that they are not unifiable with any ideographs in the current working set. The proof may be provided by listing the documents the submitter has checked, and for each proposed ideograph, a list of ideographs whose radicals and strokes have been checked against. It is an important responsibility of the submitter to check with not only the standardized CJK ideographs, but also the working set(s) submitted to WG2 for consideration and the IRG working set for any unifiable characters against its submission. If a submitter fails to do the above, the submission will not be approved by the IRG as an IRG-endorsed independent submission to WG2.

C.3. Dealing with Urgent Requests

Accepted urgently needed ideographs as independent submissions must be checked by the IRG for correctness, duplication and unification against the latest published ISO/IEC 10646 as well as the current IRG working set. When an urgently needed ideograph is found to be identical or unifiable with any ideograph in the current IRG working set, the latter must be noted and removed from the current IRG working set.

Annex D: Up-to-date CJK Unified Ideograph Sources and Source References

The IRG tracks the sources of the CJK Unified Ideographs. The past practice was that the character sources were tracked based on submissions by member bodies. Thus every member body has been assigned a member body abbreviation as defined in ISO/IEC 10646. In recognizing that submitters might be an international consortium not affiliated with any member body, the IRG decided at IRG Meeting No. 39 to add a new abbreviation "Z" for this type of submissions. It should be noted that Z source may include submissions from different projects and additional letters may be used to indicate each repertoire.

As described in Section 2.2.1.d.(5)a): "The source reference should begin with a member body abbreviation (G, H, J, K, KP, M, MY, T, UTC or V) or an international consortium abbreviation (U) followed by no more than 9 characters. It should contain only Latin capital letters and Arabic numbers to indicate the source. Numeric values to indicate the position in a specific source should be followed by a hyphen ("‐")."

Note: IRG internal documents allowed underscore ("_") to be used in source references in submissions from China and SAT until IRG Meeting No. 46. To be consistent with the ISO/IEC 10646 published standard¹⁰, the use of underscore symbol will be disallowed from any new working set submissions starting from IRG Meeting No. 47. Sources accepted in the past using underscores are thus corrected in the below list. The original reference formats are retained for cross reference to older documents only.

D.1. Member body abbreviations:

G	China
H	Hong Kong Special Administrative Region, China
J	Japan
K	Republic of Korea
KP	Democratic People's Republic of Korea
M	Macao Special Administrative Region, China
MY	Malaysia (added in Nov. 2008 at IRG Meeting No. 31)
T	Taipei Computer Association
UTC	Unicode Consortium
V	Vietnam
U	International consortium and other sources

Note: all member body abbreviations except MY are currently used in ISO/IEC 10646 Section 23. MY is defined and used by the IRG internally only.

D.2. Hanzi G sources

The format of the accepted sources is now consistent with the published standard. Code used in pointed brackets are original source references no longer supported after IRG Meeting No. 47.

G0	GB2312-80
G1	GB12345-90 with 58 Hong Kong and 92 Korean "Idu" characters
G3	GB7589-87 unsimplified forms
G5	GB7590-87 unsimplified forms
G7	General Purpose Hanzi List for Modern Chinese Language, and General List of Simplified Hanzi
GS	Singapore Characters
G8	GB8565-88
G9	GB18030-2000
GE	GB16500-95
GH	GB15564-1995 Code of Chinese Ideogram set for teltext broadcasting Hong Kong subset
GK	GB12052-89 Korean Character Coded Character Set for Information Interchange
G4K	Siku Quanshu (四庫全書) < G_4K >
GBK	Chinese Encyclopedia (中國大百科全書) < G_BK >
GCH	Ci Hai (辞海) < G_CH >
GCY	Ci Yuan (辭源) < G_CY >
GCYY	Chinese Academy of Surveying and Mapping Ideographs (中国测绘科学院用字) < G_CYY >
GDZ	Geographic Publishing House Ideographs (地质出版社用字) < G_GDZ >

¹⁰ Pages 29-33 in Section 23 of ISO/IEC 10646 4th edition, 2014-09-01

GFC	Modern Chinese Standard Dictionary (现代汉语规范词典第二版。主编：李行健。北京：外语教学与研究出版社) 2010, ISBN: 978-7-5600-9518-9
GFZ	Founder Press System (方正排版系统) < G_FZ >
GGFZ	Tongyong Guifan Hanzi Zidian (通用规范汉字字典)
GGH	Gudai Hanyu Cidian (古代汉语词典) < G_GH >
GHC	Hanyu Dacidian (漢語大詞典) < G_HC >
GHZ	Hanyu Dazidian ideographs (漢語大字典) < G_HZ > ¹¹
GIDC	ID system of the Ministry of Public Security of China, 2009 < G_IDC >
GJZ	Commercial Press Ideographs (商务印书馆用字) < G_GJZ >
GKX	GKX Kangxi Dictionary ideographs (康熙字典) 9th edition (1958) including the addendum (康熙字典) 補遺 < G_GKX >
GLGYJ	Zhuang Liao Songs Research,《壮族僚歌研究》2008年广西民族出版社, ISBN 78-7-5363-5069-4
GOCD	Oxford English-Chinese Chinese-English Dictionary (牛津英汉汉英词典。主编：Julie Kleeman, 于海江。牛津：牛津大学出版社。2010年。ISBN: 978-0-19-920761-9)
GPGLG	Zhuang Folk Song Culture Series - Pingguo County Liao Songs (壮族民歌文化丛书•平果僚歌) 2004-2006, ISBN 7-5363-[4820-7 5012-0 5013-9 5014-7 5015-5]
GRM	People's Daily Ideographs (人民日报用字) < G_GRM >
GXC	Xiandai Hanyu Cidian (现代汉语词典) < G_GXC >
GXH	Xinhua Zidian (新华字典) < G_XH >
GXHZ	Xinhua Big Dictionary (新华大字典：彩色本修订本。《新华字典》编委会编。北京：商务印书馆国际有限公司) 2011, ISBN: 978-7-80103-718-3
GWZ	Hanyu Dacidian Publishing House Ideographs (漢語大詞典出版社用字) < G_WZ >
GZ	Ancient Zhuang Character Dictionary, (古壮字字典) 1989, ISBN 7-5363-0614-8
GZFY	Hanyu Fangyan Dacidian (汉语方言大词典) < G_ZFY >
GZH	Zhonghua Zihai (中华字海) < G_ZH >
GZJW	Yinzhou Jinwen Jicheng Yinde (殷周金文集成引得) < G_ZJW >
GZYS	Chinese Ancient Ethnic Characters Research (中国民族古文字研究), 1984

D.3. Hanzi H sources

H Hong Kong Supplementary Character Set (HKSCS)

Note: The ISO/IEC 10646 published standard also included Big-5 characters as H source characters as HKSCS is considered a supplement to Big-5. The respective Big-5 characters under their categories are listed here for reference:

HB0	Big-5: Computer Chinese Glyph and Character Code Mapping Table, Technical Report C-26, 電腦用中文字型與字碼對照表，技術通報 C-26, 1984, Symbols
HB1	Big-5, Level 1
HB2	Big-5, Level 2

D.4. Hanzi T sources

T1	TCA-CNS 11643-1992 1st plane
T2	TCA-CNS 11643-1992 2nd plane
T3	TCA-CNS 11643-1992 3rd plane with some additional characters
T4	TCA-CNS 11643-1992 4th plane
T5	TCA-CNS 11643-1992 5th plane
T6	TCA-CNS 11643-1992 6th plane
T7	TCA-CNS 11643-1992 7th plane
TB	TCA-CNS 11643-2007 11th plane
TC	TCA-CNS 11643-2007 12th plane
TD	TCA-CNS 11643-2007 13th plane
TE	TCA-CNS 11643-2007 14th plane
TF	TCA-CNS 11643-2007 15th plane

D.5. Kanji J sources

J0	JIS X 0208-1990
J1	JIS X 0212-1990
J3	JIS X 0213:2000 level-3
J3A	JIS X 0213:2004 level-3 addendum from JIS X 0213:2000 level-3
J13A	JIS X 0213:2004 level-3 addendum from JIS X 0213:2000 level-3 replacing J1 characters

¹¹ As this is a modern dictionary which may be extended/revised from time to time, the IRG accepts its 1st and 2nd versions. Future extensions will be subjected to review before acceptance as appropriate IRG sources.

J13	JIS X 0213:2004 level-3 characters replacing J1 characters
JA3	JIS X 0213:2004 level-3 characters replacing JA characters
J4	JIS X 0213:2004 level-4
J14	JIS X 0213:2004 level-4 characters replacing J1 characters
JA4	JIS X 0213:2004 level-4 characters replacing JA characters JA Unified Japanese IT Vendors Contemporary Ideographs, 1993
JARIB	Association of Radio Industries and Businesses (ARIB) ARIB STD-B24 Version 5.1, March 14 2007
JH	Hanyo-Denshi Program (汎用電子情報交換環境整備プログラム), 2002-2009
JMJ	Character Information Development and Maintenance Project for e-Government "Moji-Joho-Kiban Project" (文字情報基盤整備事業), 2010-
JK	Japanese KOKUJI Collection

D.6. Hanja K sources

K0	KS C 5601-1987 (Now known as KS X 1001:2004)
K1	KS C 5657-1991 (Now known as KS X 1002:2001)
K2	PKS C 5700-1 1994 (Reedited and standardized as KS X 1027-1:2011)
K3	PKS C 5700-2 1994 (Reedited and standardized as KS X 1027-2:2011)
K4	PKS 5700-3:1998 (Reedited and standardized as KS X 1027-3:2011)K5 Korean IRG Hanja Character Set 5th Edition: 2001 (Reedited and standardized as KS X1027-4:2011)
KC	Korean History On-Line (한국 역사 정보 통합 시스템)

D.7. Hanja KP sources

KP0	KPS 9566-97
KP1	KPS 10721-2000 and KPS 10721: 2003

D.8. ChuNom V sources

V0	TCVN 5773:1993
V1	TCVN 6056:1995
V2	VHN 01:1998
V3	VHN 02: 1998
V4	Dictionary on Nom 2006, Dictionary on Nom of Tay ethnic 2006, Lookup Table for Nom in the South 1994

D.9. MY sources

MY "Dictionary Of Chinese Rustic Language In South-East Asia", written by Xu Yunqiao, published by Singapore Shjie Publisher, 1961. 《南洋华语俚俗辞典》, 新加坡世界书局有限公司, 1961 年 8 月

D.10. Macao sources

MAC Macao Information System Character Set (澳门資訊系統字集)

D.11. Unicode sources

UTC Unicode Standard Annex #45 (Unicode Version 10.0.0), June 14, 2017 (Used to be called Unicode Technical Report #45)

D.12. U sources (renamed from Z sources since IRG Meeting No. 45)

This is a new source created since IRG Meeting No. 39 to accommodate submissions from international groups working on CJK ideographs. Originally, it was named the Z source. As at the end of IRG Meeting No. 44, only one designation of SAT is used as Z_SAT for the international project of SAT for Daizōkyō. However, due to a request from WG2, this designation is renamed the U sources from IRG Meeting No. 45.

USAT Taishō Shinshū Daizōkyō (大正新脩大藏經), 1924-1934 <U_SAT>

Annex E: Maintenance Procedure of the IRG Working Document Series

E.1 Introduction

The IRG Working Document Series (IWDS) is a set of IRG maintained documents which keep the up-to-date examples of CJK unification related cases to supplement the published Annex S of ISO/IEC 10646 for IRG unification work.

E.2. IRG Working Document Series

The formats of the IWDS and the specific lists of examples are maintained as a separate set of documents as follows.

- Series 1: Summary of unification rules and examples (File name: IWDS_SUM.pdf)
- Series 2: List of Unifiable Component Variations (UCV) of Ideographs (File name: IWDS_UCV.pdf)
- Series 3: List of Non-Unifiable Components (NUC) of Ideographs and Overly-unified Ideographs (File name: IWDS_NUC.pdf)
- Series 4: List of Possibly Mis-Unified Ideographs (MUI) (File name: IWDS_MUI.pdf).


E.3. Maintenance Procedure

The maintenance procedure describes how entries in the IWDS are added, removed, or changed. The IRG has an appointed IWDS editor (currently Mr. Taichi Kawabata), who is in charge of the maintenance of the IWDS.

In principle, all update requests are results of IRG unification review work. A review cycle between two IRG meetings is needed. Every update must be discussed in at least one IRG meeting and confirmed in writing. An update normally starts from the unification review work assigned to member bodies in the past IRG meeting (Meeting No. N-1). During the review work before the next IRG meeting (Meeting No. N), if member bodies find duplicates, unifiable cases or mistakes which warrant a change in the IWDS, they need to report these cases in a specific form attached to IWD Series 1. These reported cases will then be consolidated by the IRG technical editor before IRG Meeting No. N. During IRG meeting No. N, time must be allocated to discuss these reported cases and conclusions must be recorded during this IRG meeting. Based on the confirmed conclusions on IWDS updates, the IWDS editor will update the IWDS. Any unclear conclusions will be further discussed in future meetings.

It takes time to update the IWDS, and sometimes it is difficult to find appropriate examples. The IRG has, therefore, requested the IWDS editor to keep a log of the actions carried out based on IRG instructions so that better tracking of changes can be carried out.

Below is the description of the maintenance procedure as a flow chart.



An attachment file in Excel form is more clear

Annex F: IRG Repertoire Submission Summary Form

<p>ISO/IEC JTC 1/SC 2/WG 2/IRG PROPOSAL SUMMARY FORM TO ACCOMPANY SUBMISSIONS FOR ADDITION OF CJK UNIFIED IDEOGRAPHS TO THE REPERTOIRE OF ISO/IEC 10646</p> <p>Submitters are reminded to:</p> <ol style="list-style-type: none">1. Fill in all the sections below.2. Read the Principles and Procedures Document (P & P) available at http://appsrv.cse.cuhk.edu.hk/~irg/irg/irg45/IRGN2092PnPv8.pdf for guidelines and details before filling in this form.3. Use the latest Form from http://appsrv.cse.cuhk.edu.hk/~irg/irg/irg45/IRGN2092PnP_BankDataFile.xls
<p>See also http://appsrv.cse.cuhk.edu.hk/~irg/irgwds.html for the latest <i>Unifiable Component Variations</i>.</p>

A. Administrative

1. IRG Project Code:	e.g. IRG Collection 2015
2. Title:	
3. Submitter's Region/Country Name:	
4. Submitter Type (National Body/Individual Contribution):	
5. Submission Date:	
6. Requested Ideograph Type (Unified or Compatibility Ideographs)	
If Compatibility, the submitter is strongly encouraged to instead register them as IVS in a new or an existing IVD collection(See UTS #37) with the IRG's approval (Registration fee will not be charged if authorized by the IRG.).	
7. Proposal Type (Normal Proposal or Urgently Needed)	
8. Choose one of the following: This is a complete proposal. (or) More information will be provided later.	

B. Technical – General

1. Number of ideographs in the proposal:	
2. Glyph format of the proposed ideographs: (128x128 Bitmap files or TrueType font file) If Bitmap files, are their file names the same as their source references? If TrueType font file, are all the proposed glyphs put into BMP PUA area? If TrueType font file, are data for source references vs. character codes provided?	
3. Source references: Do all the proposed ideographs have a unique, proper source reference (member body/international consortium abbreviation followed by no more than 9 alphanumeric characters)?	
4. Evidence: a. Do all the proposed ideographs have a separate evidence document which contains at least one scanned image of printed materials (preferably dictionaries)? b. Do all the printed materials used for evidence provide enough information to track them by a third party (ISBN numbers, etc.)?	
5. Attribute Data Format: (Excel file or CSV text)	

C. Technical - Checklist

Understanding of the Unification Principles

1. Has the submitter read ISO/IEC 10646 Annex S and does the submitter understand the unification principles?
2. Has the submitter read the "Unifiable Component Variations" (contact the IRG technical editor through the IRG Rapporteur for the latest version) and does the submitter understand the unifiable variation examples?
3. Has the submitter read the IRG PnP document and does the submitter understand the 5% Rule?

Character-Glyph Duplication (<http://www.itscj.ipsj.or.jp/sc2/open/pow.htm>) contains all the published ones and those under ballot)

4. Has the submitter checked that the proposed ideographs are **not unifiable** with any of the unified or compatibility ideographs of the latest version of ISO/IEC 10646?
If the checking has been done against an earlier version of ISO/IEC 10646, please specify the version. (e.g. 10646:2012)
5. Has the submitter checked that the proposed ideographs are **not unifiable** with any of the ideographs in the amendments, if any, of the latest version of ISO/IEC 10646?
If yes, which amendment(s) has the submitter checked?
6. Has the submitter checked that the proposed ideographs are **not unifiable** with any of the ideographs in the proposed amendments, if any, of ISO/IEC 10646?
If yes, which draft amendment(s) has the submitter checked?
7. Has the submitter checked that the proposed ideographs are **not unifiable** with any of the ideographs in the current working M-set and D-set of the IRG? (Contact IRG chief editor and technical editor through the IRG Rapporteur for the newest list)
If yes, which document(s) has the submitter checked?
8. Has the submitter checked that the proposed ideographs are **not unifiable** with any of the over-unified or mis-unified ideographs in ISO/IEC 10646? (See Annex E of the IRG PnP document)
9. Has the submitter checked whether the proposed ideographs have any **similar ideographs** in the current standardized or working sets mentioned above?
10. Has the submitter checked whether the proposed ideographs have any **variant ideographs** in the current standardized or working sets mentioned above?

Attribute Data

11. Do all the proposed ideographs have attribute data such as the Kangxi radical code and stroke count?
12. Are there any simplified ideographs (ideographs that are based on the policy described in 簡化字總表) among the proposed ideographs?
If yes, does the proposal include proper simplified/traditional indication flag for each proposed ideograph in the attribute data?
13. Do all the proposed ideographs have the document page number of evidence documents in the attribute data?
14. Do all the proposed ideographs have the proper Ideographic Description Sequence (IDS) in the attribute data?
If no, how many proposed ideographs do not have the IDS?
15. If the answer to question 9 or 10 is yes, do the attribute data include any information on similar/variant ideographs for the proposed ideographs?
16. Do all the proposed ideographs contain the total stroke count (kTotalStrokes)¹²?

¹² The IRG understands that kTotalStrokes can be ambiguous and subject to different interpretations.
The IRG takes no responsibility to check the correctness of the submitted attribute data.

Annex G: Examples of New CJK Unified Ideographs Submissions (i.e., Vertical Extension)

G.1. Sample Data Files


All submitted characters must follow the submission format given in Section 2.2.1. The following gives a sample list of characters submitted by UK for consideration in IRG Collection 2015(IRGN2107).

Seq.No.	a) Source reference	b) Glyph Image file name	c) KangXi Radical Code	d) Stroke Count	e) First Stroke	f) T/S (traditional 0, or simplified 1)	g) IDS (Ideographic Description Sequence)	h) Similar/ Variants	i) Ref. to Evidence doc	n) Total stroke count
61	UTC-01373	UTC-01373.bmp	62.0	4	1	0	�� ? 戈		{1} A Concordance to Fascicle Three of the Inscriptions from the Yin Ruins p. 222	8
62	UTC-01374	UTC-01374.bmp	62.0	8	3	0	�� 戟 束		{1} A Concordance to Fascicle Three of the Inscriptions from the Yin Ruins p. 223	12
63	UTC-01375	UTC-01375.bmp	63.0	11	4	0	�� 戸 商		{1} A Concordance to Fascicle Three of the Inscriptions from the Yin Ruins p. 235	15
64	UTC-01376	UTC-01376.bmp	66.0	8	3	0	�� 佳 夂	U+22F5D 钺	{1} A Concordance to Fascicle Three of the Inscriptions from the Yin Ruins p. 240	12
65	UTC-01377	UTC-01377.bmp	69.0	4	3	0	�� 午 斤		{1} A Concordance to Fascicle Three of the Inscriptions from the Yin Ruins p. 240	8
66	UTC-01378	UTC-01378.bmp	86.0	6	3	0	�� 朱 火		{1} A Concordance to Fascicle Three of the Inscriptions from the Yin Ruins p. 256	10


G.2. Sample Evidence

All character submissions must include evidence of use as specified in Section 2.2.3. The following shows an example of a Japanese submission with reference to the use of the character in ancient books (IRGN1225 Part2).

JMK66114



『補訂版国書総目録』(1969年4月30日第1刷発行, 2002年7月5日補訂版第4刷発行,
岩波書店)
第7巻 870 ページ 4段



G.3. Handling of Data with Privacy Concerns

The IRG understands that privacy laws and practices in some countries and regions can make the submission of complete records as evidence related to personal information difficult. As a compromise, the IRG suggests submitters to provide evidence in such a way that it will not reveal complete personal/internal information. However, the character information itself must be shown in the supplied evidence. In other words, partial document images should be supplied with certain sensitive information blocked.

As different departments/organizations may have different types of documents, the IRG suggests that, for each type of document, a submitter should provide a sample document with private information deleted. A good example is the original Basic Certificate of Family Relation Register in Korea as shown in Fig. G1. The evidence can be submitted as partial data in the form shown in Fig. G2.

기본증명서					
등록기준지	경상남도 김해시 내용 100번지				
구분	상세내용				
작성	【가족관계등록부작성일】 2009년 01월 01일 【자신사유】 가족관계이 등록 등에 관한 법률 부지 제3조제1항				
구분	성명	출생연월일	주민등록번호	성별	본
본인	홍길동(洪吉童)	1970년 01월 01일	700101-1*****	남	南陽
일반등록사항					
구분	상세내용				
출생	【출생장소】 경상남도 김해시 내용 100번지 【신고일】 1970년 01월 15일 【신고인】 부				
위 기본증명서는 가족관계등록부의 기록사항과 통일성을 증명합니다.					
2007년 10월 11일					
전라남도 여수시장 담사관					

Figure G1. The original Basic Certificate of Family Relation Register

기본증명서					
등록기준지	경상남도 김해시 내용 100번지				
구분	상세내용				
작성	【가족관계등록부작성일】 2009년 01월 01일 【자신사유】 가족관계이 등록 등에 관한 법률 부지 제3조제1항				
구분	성명	출생연월일	주민등록번호	성별	본
본인	홍_ _ (洪_ _)	19_ _년 _ _월 _ _일	_____ 1*****	남	
일반등록사항					
구분	상세내용				
출생	【출생장소】 _____ 【신고일】 19_ _년 _ _월 _ _일 【신고인】 부				
위 기본증명서는 가족관계등록부의 기록사항과 통일성을 증명합니다.					
2007년 10월 11일					
전라남도 여수시장 담사관					

Figure G2. A modified Basic Certificate of Family Relation Register (private information such as full name and date of birth has been deleted).

G.4. Consideration for Acceptance of Characters that Cannot be Provided in Printed Form

The consideration for acceptance of characters that cannot be provided with evidence in printed form is not meant to relax the IRG requirement in the provision of evidence of modern use. Rather, it is meant to facilitate e-government initiatives for computerized processing of

information. It is under this presumption the IRG is willing to consider acceptance of characters already supported in computer systems that are maintained by a designated government body with wide use by government bodies and citizens for administrative public service.

The IRG recognizes that some of the characters included in e-government systems cannot be provided with supporting evidence of actual use according to Section 2.2.3.a, and yet it is technically and administratively not practical to remove them from the systems. Thus the IRG is willing to consider their acceptance without actual evidence provided that they are from already implemented working systems only. However, the IRG requires the submitter to provide information on the quality assurance process for the maintenance of the character collection concerned. The submitter must supply information on the accessibility of the character collection and the working system, the stability and traceability of the collection, and the kind of evidence/information needed for approval of character removal, modification and addition by the administrative body of the collection.

Annex H [Reserved for future use]

Annex H is purposely left out for the time being so that IRG Annex numbers tally with WG2 Annex numbers where the subjects are the same.

Annex I: Guideline for Handling of CJK Ideograph Unification and/or Dis-unification Error

(Same as WG2 Principles and Procedures Annex I)

Source: www.dkuug.dk/jtc1/sc2/wg2/docs/principles.html

Below is the text extracted from Annex I of WG2 Principles and Procedures (WG2N4502) dated 2014-01-28:

There are two kinds of errors that may be encountered related to coded CJK unified ideographs.

Case 1: *to be unified* error - Ideographs that should have been unified are assigned separate code points.

Case 2: *to be disunified* error - Ideographs that should not have been unified are unified and assigned a single code point. An example of this is the request from TCA in document [N2271](#).

When such errors are found, the following guidelines will be used by WG 2 to deal with them.

I.1 Guideline for “to be unified” errors

- A. The “*to be unified*” pair will be left disunified. Once a character is assigned a code position in the standard, it will not be removed from the standard.
- B. If necessary, an additional note may be added to an appropriate section in the standard.

I.2 Guideline for “to be disunified” errors

(Source: [ISO/IEC JTC 1/SC 2/WG 2 N3859 – 2010-06-28](#))

- A. The ideographs to be disunified should be disunified and should be given separate code positions as soon as possible (disunification in some sense, and character name change in some sense also). These ideographs will have two separate glyphs and two separate code positions. One of these ideographs will stay at its current encoded position. The other one will have a new glyph and a new code position.
- B. For the ideographs that are encoded, the code charts in ISO/IEC 10646 are presented in multiple columns, with possibly differing glyph shapes in each column. The question of which glyph shall remain in the current code point will be resolved by the IRG on a case by case basis.
- C. The disunified ideograph will have a glyph that is different from the one that retains the current code position.
- D. The net result will be an addition of new ideograph character and a correction and an additional entry to the source reference table.

I.3 Discouragement of new disunification request

There is a possibility of “pure true disunification” request. This is almost like the new source code separation request. This kind of request shall not be accepted disregarding the reasoning behind. Key difference between “TO BE DISUNIFIED” and “SHALL NOT BE DISUNIFIED” is as follows.

- a. If character pair is non-cognate (meanings are different), that pair of characters is TO BE DISUNIFIED.
- b. If a character pair is cognate (means the same but different shape), that pair of characters SHALL NOT BE DISUNIFIED.

Disunification request with reason of mis-application (over-application usually) of unification rule should NOT be accepted due to the principle in resolution [M41.11](#).

Annex J: Guideline for Correction of CJK Ideograph Mapping Table Errors

(Same as WG2 Principles and Procedures Annex J)

Source: [ISO/IEC JTC 1/SC 2/WG 2 N2577 – 2003-09-02](#)

In principle, the mapping table or reference to code points of an existing national/regional standard (in the source reference tables) must not be changed. But once a fatal error is found, it should be corrected as early as possible, under the following guidelines:

J.1 Priority of Error Correction Procedure

- A. Consider adding a new code position and source-reference mapping for the character in question rather than changing the mapping table.
- B. If the change of mapping table is unavoidable, correction should be done as soon as possible.

J.2 Announcement of Addition to or Correction of Mapping Table

Once any addition to or correction of the mapping table is made, an announcement of the change should be made immediately. Usually this will be in the form of a resolution of a WG2 meeting, followed by a subsequent process resulting in an appropriate amendment to the standard.

J.3 Collection and Maintenance of Mapping Tables that are not owned by WG2

There are many mapping tables, which are included in national/regional standards or developed by third parties. These are out of WG2's scope. Any organization (such as Unicode Consortium) that collects mapping information, maintains it consistently and makes this information widely available is invited and encouraged to do so.

Annex K: List of First Strokes

Below gives the list of first strokes including their glyphs and names in English and Chinese (with pinyin provided).

Glyph	Stroke No.	Name	Name in Chinese	Pinyin
—	1	Horizontal bar	横	heng2
	2	Vertical bar	豎	shu4
＼	3	Slash	撇	pie3
、	4	Dot	點	dian3
乙	5	Turn	折	zhe2

Annex L: Guidelines for Forming Working Sets with an Upper Limit

As stated in Section 2.2.1d, the IRG sets an upper limit for the number of ideographs in a working set to ensure sufficient time for delivering quality output in a timely manner. The current limit($Limit_{IRG}$) is set to about 4,000 ideographs. Also, each memberbody submission should not go beyond 1,000 ideographs. Since the number of submissions and their repertoire sizes may differ each time when a new collection is formed, the IRG needs some basic guidelines on how the working sets can be formed in a fair manner to accommodate various needs. This Annex serves for this purpose.

At the start of the development work, submitters submit their proposals. Let us assume that the number of submissions is N .

If the total number of ideographs is less than $Limit_{IRG}$ (or reasonably close to $Limit_{IRG}$), all submissions will be used to form the working set of this collection.

If the total number of ideographs is much larger than $Limit_{IRG}$, setting an upper limit to each submission is needed. The general principle based on simple mathematic calculation is given below:

Scenario 1: The simplest case solution is that the number of ideographs from each submission should not exceed $Limit_{single_submission}$, where $Limit_{single_submission} = Limit_{IRG} / N$. This works especially well when all submission sizes are larger than $Limit_{single_submission}$.

Scenario 2: In case there is a submission with a total number of ideographs ($TOTAL_{single}$) less than $Limit_{single_submission}$, the spare quota, $Spare_{single_submission} = Limit_{single_submission} - TOTAL_{single}$, can be equally divided among those submissions which exceed $Limit_{single_submission}$. If spare quota remains afterwards, it can be divided under the same principle (recursively) among submissions which can still take the unused quota.

Even though the above mathematical method can set a quick and undisputed limit to each submission, it may not be the best solution when considering the practical needs of the submitters for different applications. Submitters are encouraged to subdivide their submission and give them priority levels with explanation and justifications. The IRG can consider these justifications and agree on a division of $Limit_{IRG}$ close to the one given in the mathematical model above with minor modifications.

It should be noted that the upper limit, $Limit_{IRG}$, is indicative and set based on the IRG's experience from past reviews that targeted for a one year review cycle. Minor modifications to this limit are allowed because unification among submissions and the withdrawal of characters by submitters can potentially reduce the total number of characters eventually included as in the repertoire for WG2 submission.

If the current collection is too large to form a single working set, the IRG will use the above principle to split the current collection into multiple working sets, and work on each of them in sequence. In this case, the subdivided sets will be named using the original call name with a subset name assigned in alphabetic sequence, eg. IRG Collection 2015A, IRG Collection 2015B, etc.

References

Document numbers in the first column in the following table refer to IRG working documents (ISO/IEC JTC 1/SC 2/WG 2/IRGNxxxx), except where noted otherwise. For documents with no link, one may try <http://www.cse.cuhk.edu.hk/~irg/>; some older documents may only be available in paper form (contact the IRG Rapporteur Prof. Qin LU).

Doc. No.	Title	Source	Date
WG2 N4502	Principles and Procedures for Allocation of New Characters and Scripts and Handling of Defect Reports on Character Names	WG2	2014-01-28
N681	Annex S http://standards.iso.org/ittf/PubliclyAvailableStandards/c039921_ISO_IEC_10646_2003(E).zip	Bruce Peterson and IRG Rapporteur	1999-11-18
N881	CJK Extension C Submission Format	IRG	2001-12-04
N953	Minutes of the adhoc meeting on submitted documents: N941, N942, N944, N945, N948, N949	CJK ad hoc group	2002-11-22
N954	Report on first stroke/stroke count by ad hoc group	CJK ad hoc group	2002-11-22
N954AR	N954 Appendix: First Stroke / Stroke Count Chart	CJK ad hoc group	2002-11-21
N955	IRG Radical Classification	Ideograph Radical Ad Hoc	2002-11-21
N956	Ideograph Unification	Ideograph Radical Ad Hoc	2002-11-21
N1105	Amendments to IRGN954AR	Macao	2005-01-03
N1183	IDS decomposition principles (Revised by the IRG)	KAWABATA, Taichi	2005-12-28
N1197	Sample evidence for CJK C1 candidates	Japan	2006-05-22
N1372	On Better use of IDS on IRG development process	KAWABATA, Taichi	2007-11-09
SC2 N3933	ISO/IEC JTC 1 Directives, 5 th Edition, Version 3.0	SC2	2007-04-06

Glossary

Abstract shape: Ideographic characters are used as symbols to represent different entities and used for different purposes. The same character conceptually can sometimes be written in different actual shapes with minor stroke differences, due to preference, which do not affect the recognition of the character as a unique symbol. These characters having the same abstract shapes are not coded separately because ISO/IEC 10646 is a character (symbol) standard, not a glyph standard. In other words, character glyphs (actual shapes) that are considered to have the same abstract shapes are to be unified under the CJK unification rules (defined in Annex S of ISO/IEC 10646).

As ideographs are formed by both the components and the relative positioning of the components, the examination of glyph difference is observed by taking into consideration the meaning, components, and their relative positions. Characters having different meanings and different actual shapes are not considered to have the same abstract shapes. Characters having the same components yet different in relative positions are generally considered to have different abstract shapes. However, component difference is subjected to examination by experts to see if they have influenced the recognition of the character as a whole with consideration of the character's origin and use. Annex S of ISO/IEC 10646 has defined the examination procedure which is given below:

- "The following features of each ideograph to be compared are examined:*
- a) the number of components,*
 - b) the relative position of the components in each complete ideograph,*
 - c) the structure of corresponding components.*

If one or more of the features a) to c) above are different between the ideographs in the comparison, the ideographs are considered to have different abstract shapes and are therefore not unified.

If all of the features a) to c) above are the same between the ideographs, the ideographs are considered to have the same abstract shape and are therefore unified."

Please also refer to Annex S in ISO/IEC 10646 for examples of characters and components that are considered to have the same abstract shape. The IRG maintains an up-to-date Unification Examples List.

Character Description Component (CDC): It refers to any symbols that can be used with the Ideograph Description Characters to form a Ideograph Description Sequence. It includes all coded CJK unified ideographs, Kangxi Radicals, CJK Radical Supplements, and coded CJK Compatibility ideographs.

CJK Unified Ideographs: It refers to the collection of unified Han characters in ISO/IEC 10646 standard. CJK stands for Chinese, Japanese and Korean. The term CJK Unified Ideographs was adopted in the earlier years of the IRG to reflect the development work of the Han character unification from the three languages at that time. It is obvious today that Han unification covers far beyond the scripts used in China, Japan and Korea. However, the term continues to be used in the standardization process and has not changed.

Compatibility Ideographs: Compatibility ideographs are defined in Section 18 of ISO/IEC 10646. Below is a direct quote from ISO/IEC 10646:2014:

"The CJK compatibility ideographs are ideographs that should have been unified with one of the CJK unified ideographs, per the unification rule described in Annex S. However, they are included in this International Standard as separate characters, because, based on various national, cultural, or historical reasons for some specific country and region, some national and regional standards assign separate code points for them."

D-set (discussion set): D-set is the set of characters that have been reviewed by IRG member bodies with pending issues which need further discussion/evidence for inclusion in the M-set of a working set.

Derived Simplified Characters: Derived Simplified Ideograph (类推简化字): A simplified ideograph whose form is derived by implicitly or explicitly applying a simplified radical, component, or rule based on the official Simplified Character List (简体字总表).

Ideographic Description Characters (IDC): The 12 characters defined in ISO/IEC 10646 starting from the code point U+2FF0: ☐☐☐☐☐☐☐☐☐☐☐☐☐

Ideographic Description Sequence (IDS): IDS describes a character using its components and indicating the relative positions of the components. IDCs are considered operators to the components. IDSs can be expressed by a context free grammar through the Backus Naur Form (BNF). The grammar G has four components:

Let $G = \{\Sigma, N, P, S\}$, where

- Σ : the set of terminal symbols including all coded radicals and coded ideographs (referred to as CDC, Character Description Components), and the 12 IDCs.
- N : the set of 5 non-terminal symbols
 $N=\{\text{IDS}, \text{IDS1}, \text{Binary_Symbol}, \text{Ternary_Symbol}, \text{CDC}\}$
- $S = \{\text{IDS}\}$, which is the start symbol of the grammar
- P : a set of rewrite rules

The following is the set of rewriting rules P:

- $\text{IDS} ::= <\text{Binary_Symbol}><\text{IDS1}><\text{IDS1}>|<\text{Ternary_Symbol}><\text{IDS1}><\text{IDS1}><\text{IDS1}>$
- $<\text{IDS1}> ::= <\text{IDS}> | <\text{CDC}>$
- $<\text{CDC}> ::= \text{coded_ideograph} | \text{coded_radical} | \text{coded_component}$
- $<\text{Binary_Symbol}> ::= \square \square | \square$
- $<\text{Ternary_Symbol}> ::= \square \square | \square$

Note1: Even though the IDCs are terminal symbols, they are not part of the CDCs.

Note2: Other than the binary symbol \square (embedment which indicate overlay of two components), all the other 11 IDCs takes the IDS components (either 2 or 3) in a specific order. The order is indicated in the following table:

--	--	--	--	--	--	--	--	--	--	--	--

Ideographic Variation Database (IVD): A database maintained by the Unicode Consortium to keep a registered Ideographic Variation Sequences as standardized ideographs. See Unicode Technical Report #37 for details¹³.

Ideographic Variation Sequence (IVS): is a sequence of two coded characters, the first being a character with the Ideographic property that is not canonically nor compatibly decomposable, the second being a variation selector character in the range U+E0100 to U+E01EF¹⁴. The first character is referred to as a base character. The purpose of IVSes are to define specific variant glyphs that are unifiable and otherwise cannot be coded according to CJK unifications. The sequence is a representation of a unifiable character glyph that is not identical to the base character. A registered IVS in IVD has a specific glyph shape defined. Once registered, a IVS can be used as other standardized ideographs.

IRG Collection: An IRG Collection refers to a collection of ideographs consolidated from submissions received upon the IRG's call for proposals. The collection is named using the year of the call in four-digit format. A collection called in 2015 is named IRG Collection 2015. An IRG collection may be split into multiple working sets to warrant effective reviews.

IRG Working Document Series (IWDS): a set of IRG maintained documents which keep the up-to-date examples of CJK unification related cases to supplement the published Annex S of ISO/IEC 10646 for IRG unification work.

M-set (main set): M-set is the set of characters that have been reviewed and accepted by IRG member bodies without pending questions in the current working set.

New Source: Any CJK source that is newly submitted by IRG member bodies which is not yet accepted by ISO/IEC 10646, thus is not present in Section 23 of ISO/IEC 10646. Member bodies may

¹³ <http://unicode.org/reports/tr37/>

¹⁴ Extracted directly from UTC Technical Report #37.

first submit their new source to the IRG for acceptance. Once accepted, the characters in that source can be accepted by the IRG for consideration for inclusion in future extensions. The IRG will also submit the source to WG2 for approval and inclusion in Section 23 of ISO/IEC 10646.

Source: A reputable published document such as a dictionary, a standardization document, or a well published and widely read or referenced book which is accepted by the IRG as authoritative such that the characters in this source are considered reliable, stable, and suitable for consideration of inclusion. A set of ISO/IEC 10646 accepted sources is listed in Section 23 of the ISO/IEC 10646 document.

Urgently Needed Characters: Urgently Needed Characters are a collection of ideographs submitted by a member body or an ISO recognized organization with a size no bigger than 30 (normally). If the submitter can demonstrate an urgent need for the ideographs to be standardized for justifiable reasons, the IRG will accept them for review and endorsement to WG2 for acceptance independent of the current working set. The IRG will not initiate any call for urgently needed characters.

Working set: A working set is the set of characters accepted by the IRG as a collection or part of a collection to work on for extension to ISO/IEC 10646. Characters accepted in a working set are subject to review by IRG member bodies for inclusion in a particular extension. The IRG uses the year of the call in four-digit format to name its new collections. If a new collection is split into multiple working sets, an additional alphabet letter will be used to name these working sets.